


Plan 2

Figure 8



4 beds are 4' x 8' x 1' and there is eight 4' Drip Lines in each, ending with a plug. Four on the left and four on the right of the Mainline Tubing.

To get the MainLine up and over each bed, you will need four elbows for the first three beds and two elbows for the last bed, connecting them all with cut sections of MainLine Tubing and ending the line on the last bed with a Figure 8.

There should be at least Four Rain Barrels elevated 4 ft. for the system to work at its best.

